

**GENERAL NOTES:**

- REFER TO PAGE A.000.1 - PROJECT INFO, GENERAL NOTES & CODE INFO, FOR MORE INFORMATION.
- REFER TO PAGE A.006.1 - ACCESSIBILITY DETAILS FOR TAS AND ACCESSIBILITY INFORMATION.





**GENERAL ROOF NOTES:**

- A. BUILDING EXPANSION JOINT PER PRE-ENGINEERED BUILDING MANUFACTURER AND STRUCTURAL ENGINEER'S RECOMMENDATIONS.
- B. NO LARGE PENETRATIONS THROUGH STANDING SEAM ROOFS (STACK VENTS, LOCATED OUT OF VIEW OR BEHIND PARAPET WALLS ARE OK).


**MINIMUM GUTTER AND DOWNSPOUT REQUIREMENTS:**

**PROPOSED MINIMUM DOWNSPOUT CALCULATION**

GUTTER: MIN. WIDTH = 8"  
MIN DEPTH = 8"  
EACH SLOPE ROOF AREA: 12,545 SF  
RATIO: 1/125  
12,545 / 125 = 100.4 SQ. IN. OF DOWNSPOUT AREA  
PROPOSED DOWNSPOUT MIN = 6"X5" = 30 SQ. IN.  
(4) FOUR DOWNSPOUTS = 120 SQ. IN.



DATE	REVISION	DESCRIPTION
07/10/17	ISSUED AS BACKGROUND	
08/16/17	ISSUED AS UPDATED BACKGROUND	
10/17/17	ISSUED FOR PERMIT	
01/09/18	SITE REVISION	
01/15/18	INTERIM REVISION	
01/24/18	ISSUED FOR PERMIT	
03/08/18	CLIENT REVISION	
05/09/18	ADDRESS REVISION	
09/04/18	CC REVISION	
02/27/19	COORDINATION ISSUANCE	
08/07/19	ISSUED FOR CONSTRUCTION	
08/07/19	CLIENT REVISION	
08/07/19	CLIENT REVISION	



**TOMORROW PLANNING, INC.**  
JOHN T. MARROW  
PROPRIETARY INFORMATION  
THIS DRAWING IS THE PROPERTY OF TOMORROW PLANNING, INC. NO PART OF ANY DESIGN INFORMATION CONTAINED HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT PERMISSION IN WRITING FROM THE ARCHITECT.  
COPYRIGHT © 1989-2011

**PARK PID**  
5701 PARK PID RD  
CORPUS CHRISTI, TX 78406

**SITE PLAN**

INITIAL DATE: DRAWN BY:  
SCALE: AS SHOWN CHK'D BY:  
DWG. NO.:  
PROJECT NO. 1705

SHEET NO.  
**A 1.2**